AL_17County_2020_B20



Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 2.1	Primary Contractor: Digital Aerial Solutions LLC (DAS)	
Las Version: 1.4	Contract Mechanism: GPSC	
P Method: 7 - Linear-Mode Lidar		
Collection Start Date: 12-09-2020	Collection End Date: 02-23-2021	
The National Map Email: tnm_help@usgs.gov		

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy	II IOAI POINI (IOUO		Digital Elevation Model	
of the lidar and lidar-derived bare earth DEM data at the project level	Required Value(cm)	Tested Value (cm)	Required Value(cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-Percent Confidence Level	19.6	8.14	19.6	8.33
Vegetated Vertical Accuracy 95th Percentile	N/A	12.39	30.0	13.43

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.			
Classification ID	Classification Type		
1	Processed, but unclassified		
2	Bare earth		
7	Low noise		
9	Water		
17	Bridge deck		
18	High noise		
20	Ignored ground (typically breaklines proximity)		
21	Snow (if present and identifiable)		
22	Temporal exclusion (typically nonfavored data in intertidal zones)		

Sensor(s) Used

Sensor
Riegl VQ-1560i - Aerial Oscillating Mirror
Leica Terrain Mapper - Aerial Oscillating Mirror





Project Name: AL_17County_2020_B20

Report Date: 2022-07-21

Work Unit Information

AL_17Co_2_2020	Work Unit ID: 226776	Quality Level: 2	
Horizontal EPSG Code: 6345	Vertical EPSG Code: 5703	Geoid Model: GEOID 18	
DEM Ground Sample Distance: 1.0	Hydro Treatment: hydro-flattened		
Collection Start Date: 2020-12-10	Collection End Date: 2021-01-17		

AL_17Co_1_2020	Work Unit ID: 191531	Quality Level: 2		
Horizontal EPSG Code: 6345	Vertical EPSG Code: 5703	Geoid Model: GEOID 18		
DEM Ground Sample Distance: 1.0	Hydro Treatment: hyd	Hydro Treatment: hydro-flattened		
Collection Start Date: 2020-12-09	Collection End Date:	Collection End Date: 2021-02-23		





Project Name: AL_17County_2020_B20

Report Date: 2022-07-21