FL_Everglades NP LiDAR_2017_D16



Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 1.2	Primary Contractor: Dewberry Consultants LLC (Dewberry)	
Las Version: 1.4	Contract Mechanism: GPSC	
P Method: 13 - Topobathymetric Lida		
Collection Start Date: 04-19-2017	Collection End Date: 06-12-2017	
The National Map Email: tnm_help@usgs.gov		

Vertical Accuracy Results- Please see the vertical_accuracy folder within the project metadata for more information.

The U.S. Geological Survey evaluates absolute vertical accuracy	Lidar Point Cloud		Digital Elevation Model	
of the lidar and lidar-derived bare earth DEM data at the project level	Kequired	Tested Value (cm)	IKeamrea	Tested Value (cm)
Non-Vegetated Vertical Accuracy	19.6	7.29	19.6	7.11
95-Percent Confidence Level	19.0	1.29	19.0	7.11
Vegetated Vertical Accuracy	N/A	33.51	29.4	33.97
95th Percentile	IN/A	33.31	29.4	33.91
Bathymetric Vertical Accuracy				
95-Percent Confidence Level	36.3	38.73	36.3	39.66

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.			
Classification ID	Classification Type		
1	Processed, but unclassified		
2	Bare earth		
7	Low noise		
9	Water		
17	Bridge decks		
18	High noise		
40	Bathymetric Bottom		
41	Water Surface		
45	Water Column		

Sensor(s) Used

Sensor	
Riegl LMS-Q680i - Rotating Polygon Mirror	
Riegl VQ820G - Topo-Hydrographic Airborne Laser Scanner	





Project Name: FL_Everglades NP LiDAR_2017_D16

Report Date: 2023-03-15

Work Unit Information

FL_Everglades_N_2017	Work Unit ID: 58896	Quality Level: 1
Horizontal EPSG Code: 6346	Vertical EPSG Code: 5703	Geoid Model: GEOID12B
DEM Ground Sample Distance: 0.5	Hydro Treatment: no hyd	dro treatment
Collection Start Date: 2017-04-19	Collection End Date: 20 3	17-05-30

FL_Everglades_S_2017	Work Unit ID: 78417	Quality Level: 1	
Horizontal EPSG Code: 6346	Vertical EPSG Code: 5703	Geoid Model: GEOID12B	
DEM Ground Sample Distance: 0.5	Hydro Treatment: no hy	Hydro Treatment: no hydro treatment	
Collection Start Date: 2017-04-19	Collection End Date: 20	17-06-12	





Project Name: FL_Everglades NP LiDAR_2017_D16

Report Date: 2023-03-15