# IA\_WesternIA\_2020\_D21



**Project Definition:** The entire collection for a contracted area.

**Work Unit Definition:** A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

## **Project Information**

Lidar Base Specification: 2020 Revision A	Primary Contractor: Aerial Services, Inc. (ASI)
Las Version: 1.4	Contract Mechanism: GPSC
P Method: 7 - Linear-Mode Lidar	
Collection Start Date: 11-27-2020	Collection End Date: 04-01-2021
The National Map Email: tnm_help@usgs.gov	

### **Vertical Accuracy Results**

The U.S. Geological Survey evaluates absolute vertical accuracy	II IOAF POINT CIOUO		Digital Elevation Model	
of the lidar and lidar-derived bare earth DEM data at the project level	Required Value(cm)	Tested Value (cm)	Required Value(cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-Percent Confidence Level	19.6	9.54	19.6	10.82
Vegetated Vertical Accuracy 95th Percentile	N/A	13.78	30.0	15.50

Please see the vertical accuracy folder within the project metadata for more information.

#### Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.		
Classification ID	Classification Type	
1	unclassified	
2	ground	
7	low noise	
9	water	
17	bridge deck	
18	high noise	
20	ignored ground	

# Sensor(s) Used

Sensor
Optech Galaxy ALTM - Aerial Oscillating Mirror
Optech Galaxy T2000 - Aerial Oscillating Mirror
Leica ALS70 - Aerial Oscillating Mirror
Optech Galaxy T500 - Aerial Oscillating Mirror.





Project Name: IA\_WesternIA\_2020\_D21

Report Date: 2022-09-08

## **Work Unit Information**

IA_Western_2_2020	Work Unit ID: 224117	Quality Level: 2
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID 18
<b>DEM Ground Sample Distance:</b> 1.0	Hydro Treatment: hydro-	-flattened
Collection Start Date: 2020-11-27	<b>Collection End Date: 202</b>	21-04-01

IA_Western_3_2020	Work Unit ID: 224114	Quality Level: 2
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID 18
<b>DEM Ground Sample Distance: 1.0</b>	<b>Hydro Treatment:</b> hydr	o-flattened
Collection Start Date: 2020-12-05	Collection End Date: 2	021-03-28

IA_Western_1_2020	Work Unit ID: 212607	Quality Level: 2
Horizontal EPSG Code: 6343	Vertical EPSG Code: 5703	Geoid Model: GEOID 18
<b>DEM Ground Sample Distance: </b> 1.0	Hydro Treatment: hydro-flattened	
Collection Start Date: 2020-11-27	Collection End Date: 2021-03-29	





Project Name: IA\_WesternIA\_2020\_D21

Report Date: 2022-09-08