

Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 2021 Revision A	Primary Contractor: The Sanborn Map Company, Inc. (Sanborn)		
Las Version: 1.4	Contract Mechanism: Contributed		
P Method: 7 - Linear-Mode Lidar			
Collection Start Date: 11-12-2021 Collection End Date: 11-20-2021			
The National Map Email: tnm_help@usgs.gov			

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy of the lidar and lidar-derived bare earth DEM data at the project level

Lidar Point Cloud	Required NVA RMSEz (cm)	NVA RMSF7	95% confidence			Tested VVA at 95th percentile (cm)
	10.0	7.86	19.6	15.40	N/A	17.93

Digital Elevation Model	NVA	NVA BMSE7	95% confidence	95% confidence		Tested VVA at 95th percentile (cm)
	10.0	7.89	19.6	15.47	30.0	17.82

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.

Classification ID	Classification Type	
1	Processed, but Unclassified	
2	Bare Earth ground	
7	Low Noise	
9	Water	
17	Bridge Decks	
18	High Noise	
20	Ignored Ground	
21	Snow	
22	Temporal Exclusion	

Sensor(s) Used





Sensor

Leica Terrain Mapper - Aerial Oscillating Mirror





Project Name: LA_2021GreaterNewOrleans_C22

Work Unit Information

LA_2021GNO_1_C22	Work Unit ID: 300052	Quality Level: 1	
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18	
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened		
Collection Start Date: 2021-11-12	Collection End Date: 2021-11-20		





Project Name: LA_2021GreaterNewOrleans_C22