

Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 2021 Revision A	Primary Contractor: Merrick-Surdex Joint Venture (MSJV)
Las Version: 1.4	Contract Mechanism: GPSC
P Method: 7 - Linear-Mode Lidar	
Collection Start Date: 05-23-2022	Collection End Date: 07-30-2022
The National Map Email: tnm_help@usgs.gov	

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy of the lidar and lidar-derived bare earth DEM data at the project level

Lidar Point Cloud	Required NVA RMSEz (cm)	Tested NVA RMSEz (cm)	Required NVA at 95% confidence level (cm)	Tested NVA at 95% confidence level (cm)	Required VVA at 95th percentile (cm)	Tested VVA at 95th percentile (cm)
	10.0	6.02	19.6	6.02	N/A	18.56

Digital Elevation Model	Required NVA RMSEz (cm)	Tested NVA RMSEz (cm)	Required NVA at 95% confidence level (cm)	Tested NVA at 95% confidence level (cm)	Required VVA at 95th percentile (cm)	Tested VVA at 95th percentile (cm)
	10.0	5.96	19.6	11.69	30.0	18.48

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.	
Classification ID	Classification Type
1	Unclassified
2	ground
7	low noise
9	water
17	bridge
18	high noise
20	ignored ground

Sensor(s) Used

Sensor
Optech Galaxy T2000 - Aerial Oscillating Mirror

Work Unit Information

MN_UpperMissRiver_5_B22	Work Unit ID: 300141	Quality Level: 1
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2022-06-09	Collection End Date: 2022-07-18	

MN_UpperMissRiver_3_B22	Work Unit ID: 300139	Quality Level: 1
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2022-05-23	Collection End Date: 2022-07-30	

MN_UpperMissRiver_6_B22	Work Unit ID: 300142	Quality Level: 1
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2022-05-23	Collection End Date: 2022-07-16	

MN_UpperMissRiver_1_B22	Work Unit ID: 230955	Quality Level: 1
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2022-05-23	Collection End Date: 2022-07-30	

MN_UpperMissRiver_2_B22	Work Unit ID: 300138	Quality Level: 1
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2022-05-23	Collection End Date: 2022-07-02	

MN_UpperMissRiver_4_B22	Work Unit ID: 300140	Quality Level: 1
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2022-06-09	Collection End Date: 2022-07-27	