

**Project Definition:** The entire collection for a contracted area.

**Work Unit Definition:** A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

## Project Information

<b>Lidar Base Specification:</b> 1.3	<b>Primary Contractor:</b> Quantum Spatial, Inc
<b>Las Version:</b> 1.4	<b>Contract Mechanism:</b> GPSC
<b>P Method:</b> 7 - Linear-Mode Lidar	
<b>Collection Start Date:</b> 02-19-2019	<b>Collection End Date:</b> 04-09-2020
<b>The National Map Email:</b> tnm_help@usgs.gov	

## Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy of the lidar and lidar-derived bare earth DEM data at the project level	Lidar Point Cloud		Digital Elevation Model	
	Required Value(cm)	Tested Value (cm)	Required Value(cm)	Tested Value (cm)
<b>Non-Vegetated Vertical Accuracy</b>				
95-Percent Confidence Level	19.6	8.78	19.6	9.26
<b>Vegetated Vertical Accuracy</b>				
95th Percentile	N/A	16.04	30.0	18.29

Please see the vertical\_accuracy folder within the project metadata for more information.

## Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.	
Classification ID	Classification Type
1	Processed, But Unclassified
2	Bare Earth
7	Low Noise
9	Water
17	Bridge Decks
18	High Noise
20	Ignored Ground

## Sensor(s) Used

Sensor
Riegl LMS Q1560 - Aerial Rotating Prism
Riegl VQ-1560i - Aerial Oscillating Mirror
Optech Galaxy Prime - Aerial Oscillating Mirror

## Work Unit Information

<a href="#">MO_WestCentral_2_2018</a>	<b>Work Unit ID:</b> 175527	<b>Quality Level:</b> 1
<b>Horizontal EPSG Code:</b> 6344	<b>Vertical EPSG Code:</b> 5703	<b>Geoid Model:</b> GEOID 12B
<b>DEM Ground Sample Distance:</b> 0.5	<b>Hydro Treatment:</b> hydro-flattened	
<b>Collection Start Date:</b> 2019-02-19	<b>Collection End Date:</b> 2020-03-06	

<a href="#">MO_WestCentral_1_2018</a>	<b>Work Unit ID:</b> 176740	<b>Quality Level:</b> 2
<b>Horizontal EPSG Code:</b> 6344	<b>Vertical EPSG Code:</b> 5703	<b>Geoid Model:</b> GEOID 12B
<b>DEM Ground Sample Distance:</b> 1.0	<b>Hydro Treatment:</b> hydro-flattened	
<b>Collection Start Date:</b> 2019-12-03	<b>Collection End Date:</b> 2020-02-02	

<a href="#">MO_WestCentral_4_2018</a>	<b>Work Unit ID:</b> 197880	<b>Quality Level:</b> 2
<b>Horizontal EPSG Code:</b> 6344	<b>Vertical EPSG Code:</b> 5703	<b>Geoid Model:</b> GEOID 12B
<b>DEM Ground Sample Distance:</b> 1.0	<b>Hydro Treatment:</b> hydro-flattened	
<b>Collection Start Date:</b> 2019-12-07	<b>Collection End Date:</b> 2020-02-22	

<a href="#">MO_WestCentral_3_2018</a>	<b>Work Unit ID:</b> 196680	<b>Quality Level:</b> 2
<b>Horizontal EPSG Code:</b> 6344	<b>Vertical EPSG Code:</b> 5703	<b>Geoid Model:</b> GEOID 12B
<b>DEM Ground Sample Distance:</b> 1.0	<b>Hydro Treatment:</b> hydro-flattened	
<b>Collection Start Date:</b> 2019-12-12	<b>Collection End Date:</b> 2020-04-09	