

Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Project ID: 80403

Lidar Base Specification: 1.3	Primary Contractor: Woolpert, Inc
Las Version: 1.4	Contract Mechanism: GPSC
P Method: 7 - Linear-Mode Lidar	Hydro Treatment: hydro-flattened
Collection Start Date: 01-08-2019	Collection End Date: 03-07-2019
The National Map Email: tnm_help@usgs.gov	

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy of the lidar and lidar-derived bare earth DEM data at the project level	Lidar Point Cloud		Digital Elevation Model	
	Required Value (cm)	Tested Value (cm)	Required Value (cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-percent confidence level	19.6	9.56	19.6	9.76
Vegetated Vertical Accuracy 95th Percentile	N/A	19.52	30.0	18.72

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.

Classification ID	Classification Type
1	Processed but not classified
2	Bare earth ground
7	Noise
9	Water
17	Bridge Decks

Sensor(s) Used

Sensor
Riegl LMS Q1560 - Aerial Rotating Prism
Optech Galaxy Prime - Aerial Oscillating Mirror
Optech Galaxy Prime - Aerial Oscillating Mirror
Riegl LMS Q1560 - Aerial Rotating Prism

18	High Noise
20	Ignored ground

Work Unit Information

OK_Panhandle_B1C_2018	Work Unit ID: 185925	Quality Level: 2
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: N/A
DEM Ground Sample Distance: 1.0		
Collection Start Date: 02-25-2019	Collection End Date: 03-07-2019	

OK_Panhandle_B1A_2018	Work Unit ID: 80400	Quality Level: 2
Horizontal EPSG Code: 6342	Vertical EPSG Code: 5703	Geoid Model: N/A
DEM Ground Sample Distance: 1.0		
Collection Start Date: 01-16-2019	Collection End Date: 03-01-2019	

OK_Panhandle_B1B_2018	Work Unit ID: 185919	Quality Level: 2
Horizontal EPSG Code: 6343	Vertical EPSG Code: 5703	Geoid Model: N/A
DEM Ground Sample Distance: 1.0		
Collection Start Date: 01-30-2019	Collection End Date: 03-07-2019	

OK_Panhandle_B2_2018	Work Unit ID: 80406	Quality Level: 2
Horizontal EPSG Code: 6343	Vertical EPSG Code: 5703	Geoid Model: N/A
DEM Ground Sample Distance: 1.0		
Collection Start Date: 01-08-2019	Collection End Date: 03-07-2019	