Elevation QC Report

OR_CVO-Newberry-Del2_2010 **Project:**

Watershed Sciences Contractor:

Data Delivery Date:

06/23/2011

Date Data Reviewed:

08/16/2011

3.0 feet

Reviewer:

Hannah Boggs

Total Square Miles Reviewed:

248.78 square miles

Elevation Type: LIDAR Format: LAS

Grid Spacing:

Tile size: 7.5' by 7.5'

Projection:LCC

Datum: NAD83

Units: International Feet

Licensing: Public Domain

Metadata: Project Level

Materials Received:

LAS

All Points (classified LAS)

Grounds (Bare Earth LAS)

Shapefiles:

Ground Control Points

(Newberry ALL RTK.shp)

Tiling Scheme Shapefile for LAS

(Newberry 0 75 QUADS OGIC.shp)

Tiling Scheme Shapefile for DEM

(Newberry 7 5 QUADS OGIC.shp)

Project Footprint Shapefile

(Newberry Delivery Area 2.shp)

Newberry Processing Bins

(Newberry Processing Bins.shp)

Rasters:

Digital Elevation Models (DEM's)

Ground Density Rasters

Intensity files

Highest Hit (1st returns)

Metadata:

DEM metadata (will function as project metadata) (xml format)

Metadata for all shapefiles delivered (xml format)

Metadata for all rasters delivered (xml format)

Data report for entire project from Watershed Sciences (.pdf format)

Data acceptance report from DOGAMI (.pdf format)

See below

Vertical Accuracy Notes:

Reviewer was unable to conduct a Vertical Accuracy test due to a lack of check points that were of a higher accuracy than the LiDAR data.

Vertical Accuracy of the data was calculated by the contractor. Contractor used Real Time Kinematic (RTK) ground survey points. Reviewer approves collection method, distribution, and amount of points collected for this dataset. There were 4,062 RTK points well distributed throughout Newberry deliveries 1, 2, and 3.

Reported RMSE is 0.12 feet.

Reported standard deviation (2 sigma): 0.23 feet.

Please see QC Review Summary and NED processing Steps on the following two pages.

DELIVERABLES:

Trajectory files were not received. All other deliverables were received. Reviewer checked completeness and formatting in Global Mapper and ArcMap. In the "OLC Newberry Delivery 2 Acceptance Report" it states that all delivered data are projected as Oregon Lambert, NAD 83 (HARN), Intl Feet. The reviewer found that the shapefiles "Newberry_ALL_RTK" and "Newberry_Processing_Bins" are both projected in UTM Zone 10, NAD 83, units in meters. All other deliverables received match formatting guidelines detailed in the "OLC Newberry Delivery 2 Acceptance Report".

METADATA:

Metadata for the DEM datasets that will function as the project level metadata were run through the Metadata Parser in ArcCatalog. While general information is included and the metadata files reference the FGDC Content Standards for Digital Geospatial Metdata, the metadata parser came up with 25 errors. Metadata is in xml format. These errors will be detailed later in this document.

Reviewer fixed as many errors as possible and created a new project level metadata file for the NED titled OR_CVO-Newberry-Del2_2010.xml. This is the best use metadata file for this project. It is located under the METADATA - Documents folder.

LAS:

Reviewer loaded the classified LAS "all returns" into Global Mapper. LAS was tiled in a 100th quad scheme. Classifications reviewer was able to identify in Global Mapper included unclassified and ground.

Reviewer loaded the LAS "grounds" into Global Mapper. LAS conformed to the 100th quad tiling scheme. Global Mapper filter showed only "ground" classification for these points. One issue the reviewer found with the LAS "ground" classified points was that most waterbodies contained points classified as "ground". An example is provided below.

DIGITAL ELEVATION MODELS:

Reviewer loaded the ArcGrids into a Global Mapper Catalog for review. Reviewer used UTM Zone 10 projection in the review. The data was examined at an average scale of 1:5200 throughout the project area.

There was no requirement for treatment of waterbodies or double line streams, therefore waterbodies are not flattened and double line streams have not been forced to drain downhill. Reviewer created an errors shapefile showing waterbodies that have not been flattened for reference purposes. Examples are provided below.


Bare earth surface is good. Through the majority of the project, there is not excessive "over-editing" of the bare earth points. Most vegetation, bridges, and buildings appear to be removed properly. Reviewer created an errors shapefile showing buildings that were not completely removed. Examples are provided below. Reviewer found artifacts along the edges of tiles. Such artifacts are included in the errors shapefile. Examples are provided below. The surface is free from very high points that are most likely noise, and quilting.

This data is recommended for NED 1/9th.


PROCESSING STEP FOR THE NED:


Reviewer loaded the ArcGrids into ArcMap. Using the Mosaic to Raster Model, reviewer created a large ArcGrid file. Reviewer loaded all provided DEM datasets into the Mosaic To New Raster model. The reviewer used the 32 bit float parameter, and the blend method because there were over-lapping tiles. Reviewer kept original projection and resolution (UTM Zone 10 NAD 83, 1.00 meter cell size).

OR_CVO-Newberry-Del2_2010: Project Area




OR CVO-Newberry-Del2 2010: Project Area Hillshade













OR_CVO-Newberry-Del2_2010: Example of Building (1) Not Removed (3D)









OR_CVO-Newberry-Del2_2010: Example of Building (2) Not Removed (3D)







OR_CVO-Newberry-Del2_2010: Example of Artifact

Scale = 1:1017




OR_CVO-Newberry-Del2_2010: Example of Waterbodies Not Flattened






OR_CVO-Newberry-Del2_2010: Example of Waterbodies Not Flattened (2)

Scale = 1:2136



OR CVO-Newberry-Del2 2010: Example of Double Line Stream Not Forced to Flow Downstream

Scale = 1:2860



OR CVO-Newberry-Del2 2010: Errors Revealed in Metadata Parser

```
Start Time: Tue Aug 16 13:52:33 2011
Running script mp...
H:\CVO NEWBERRY CRATER\CVO NEWBERRY DEL2\RASTERS\DEMS\BARE EARTH\be 43121g1\metadata.xml
: mp 2.9.6 - Peter N. Schweitzer (U.S. Geological Survey)
: Info: input file =
H:\CVO NEWBERRY CRATER\CVO NEWBERRY DEL2\RASTERS\DEMS\BARE EARTH\be 43121g1\metadata.xml
: Error (line 10): improper value for Publication Date
: Error (line 22): improper value for Beginning Date
: Error (line 22): improper value for Ending Date
: Error (line 48): Place Keyword Thesaurus is required in Place
: Error (line 84): Horizontal Positional Accuracy Report is required in
Horizontal Positional Accuracy
: Error (line 85): Horizontal Positional Accuracy Value is required in
Quantitative Horizontal Positional Accuracy Assessment
: Error (line 89): Vertical Positional Accuracy Report is required in
Vertical Positional Accuracy
: Error (line 91): improper value for Vertical Positional Accuracy Value
: Error (line 97): Process Date is required in Process Step
: Error (line 102): Process Date is required in Process Step
: Error (line 137): Entity Type Label is required in Entity Type
: Error (line 137): Entity_Type_Definition is required in Entity_Type
: Error (line 137): Entity Type Definition Source is required in Entity Type
: Error (line 147): Attribute Definition is required in Attribute
: Error (line 147): Attribute Definition Source is required in Attribute
: Error (line 147): Attribute Domain Values is required in Attribute
: Error (line 150): Attribute Definition is required in Attribute
: Error (line 150): Attribute Definition Source is required in Attribute
: Error (line 150): Attribute Domain Values is required in Attribute
: Error (line 155): Distribution Liability is required in Distribution Information
: Error (line 157): Contact Voice Telephone is required in Contact Information
: Error (line 162): Address Type is required in Contact Address
: Error (line 172): Fees is required in Standard Order Process
: Error (line 173): Digital Transfer Option is required in Digital Form
: Error (line 174): Format Name is required in Digital Transfer Information
: 25 errors: 21 missing, 4 bad value
Completed script mp...
Executed (mp) successfully.
End Time: Tue Aug 16 13:52:33 2011 (Elapsed Time: 0.00 seconds)
```

```
Executing: mp
 H:\CVO NEWBERRY CRATER\CVO NEWBERRY DEL2\RASTERS\DEMS\BARE EARTH\be 43121g1\metadata.xml
 Start Time: Tue Aug 16 14:00:41 2011
 Running script mp...
 H:\CVO NEWBERRY CRATER\CVO NEWBERRY DEL2\RASTERS\DEMS\BARE EARTH\be 43121g1\metadata.xml
 : mp 2.9.6 - Peter N. Schweitzer (U.S. Geological Survey)
 : Info: input file =
 H:\CVO NEWBERRY CRATER\CVO NEWBERRY DEL2\RASTERS\DEMS\BARE EARTH\be 43121q1\metadata.xml
 : Error (line 87): improper value for Horizontal Positional Accuracy Value
 : Error (line 102): Process Date is required in Process Step
 : Error (line 137): Entity Type Label is required in Entity Type
 : Error (line 137): Entity Type Definition is required in Entity Type
 : Error (line 137): Entity Type Definition Source is required in Entity Type
 : Error (line 147): Attribute Definition is required in Attribute
 : Error (line 147): Attribute Definition Source is required in Attribute
 : Error (line 147): Attribute Domain Values is required in Attribute
 : Error (line 150): Attribute Definition is required in Attribute
 : Error (line 150): Attribute Definition Source is required in Attribute
 : Error (line 150): Attribute Domain Values is required in Attribute
 : Error (line 155): Distribution Liability is required in Distribution Information
 : Error (line 157): Contact Voice Telephone is required in Contact Information
 : Error (line 162): Address Type is required in Contact Address
 : Error (line 172): Fees is required in Standard Order Process
 : Error (line 173): Digital Transfer Option is required in Digital Form
 : Error (line 174): Format Name is required in Digital Transfer Information
 : 17 errors: 16 missing, 1 bad value
 Completed script mp...
 Executed (mp) successfully.
End Time: Tue Aug 16 14:00:41 2011 (Elapsed Time: 0.00 seconds)
```

