AK_Juneau_Landslide_2021_D21



Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 2020 Revision A	Primary Contractor: Quantum Spatial Inc. (QSI)
Las Version: 1.4	Contract Mechanism: GPSC
P Method: 7 - Linear-Mode Lidar	
Collection Start Date: 06-28-2021	Collection End Date: 08-22-2021
The National Map Email: tnm_help@usgs.gov	,

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy			Digital Elevation Model	
of the lidar and lidar-derived bare earth DEM data at the project level	Required Value(cm)	Tested Value (cm)	Required Value(cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-Percent Confidence Level	9.8	3.12	9.8	3.72
Vegetated Vertical Accuracy 95th Percentile	N/A	7.01	15.0	3.96

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.			
Classification ID	Classification Type		
1	unclassified		
2	ground		
7	low noise		
9	water		
17	bridge deck		
18	high noise		
20	ignored ground		
21	Temporal Exclusion		
22	Snow		

Sensor(s) Used

Sensor
Riegl VQ-1560ii - Rotating Polygonal Mirror





Project Name: AK_Juneau_Landslide_2021_D21

Report Date: 2022-06-29

Work Unit Information

AK_Juneau_Landslide_1_2021	Work Unit ID: 221065	Quality Level: 0
Horizontal EPSG Code: 6337	Vertical EPSG Code: 5703	Geoid Model: GEOID 12B
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2021-06-28	Collection End Date: 202	21-08-22

AK_Juneau_Landslide_2_2021	Work Unit ID: 225015	Quality Level: 0
Horizontal EPSG Code: 6337	Vertical EPSG Code: 5703	Geoid Model: GEOID 12B
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened	
Collection Start Date: 2021-06-28	Collection End Date: 2021-08-22	





Project Name: AK_Juneau_Landslide_2021_D21

Report Date: 2022-06-29