CA_FEMAR9PanocheSanLuis_2019_D2

O Project Summary



Work Package ID: 186405

Work Package Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per work package.

Project Information

Lidar Base Specification: 2.1	Primary Contractor: Woolpert, Inc	
Las Version: 1.4	Contract Mechanism: GPSC	
P Method: 7 - Lidar	Hydro Treatment: Hydroflatten	
Collection Start Date: 2020-01-04	Collection End Date: 2020-01-19	
The National Map Email: tnm_help@usgs.gov		

Vertical Accuracy Results

The U.S. Geological Survey evaluates	Lidar Point Cloud		Digital Elevation Model	
absolute vertical accuracy of the lidar and lidar-derived bare earth DEM data at the work package level	Required Value (cm)	Tested Value (cm)	Required Value (cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-percent confidence level	19.6	5.59	19.6	7.81
Vegetated Vertical Accuracy 95th Percentile		14.91	30.0	23.02

Please see the vertical_accuracy folder within the work package metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable		
Lidar Base Specification. Classifications beyond the minimum are not		
verified by USGS.		
Classification ID	Classification Type	
1	Processed, But Unclassified	
2	Bare Earth	
7	Low Noise	
9	Water	
10	Ignored Ground	
17	Bridge Decks	

Sensor(s) Used

Sensor	
Optech Galaxy ALTM - Aerial Oscillating	M

g Mirro

18 H	igh Noise
------	-----------

Work Unit Information

CA_FEMAR9PanocheSanLuis_2019	Work Unit ID: 186402	Quality Level: 2
Horizontal EPSG Code: 6339	Vertical EPSG Code: 5703	Geoid Model: GEOID 12B
DEM Ground Sample Distance: 1.0	Units: Meters	
Collection Start Date: 2020-01-04	Collection End Date: 2020-0	1-19

Internal Comments:

None