

Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 2020 Revision A	Primary Contractor: Merrick-Surdex Joint Venture (MSJV)			
Las Version: 1.4	Contract Mechanism: GPSC			
P Method: 7 - Linear-Mode Lidar				
Collection Start Date: 05-15-2022	Collection End Date: 09-18-2022			
The National Map Email: tnm_help@usgs.gov				

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy	II IOAF POINT CIOUO		Digital Elevation Model	
	Rodilirod		Required Value(cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-Percent Confidence Level	19.6	7.16	19.6	7.28
Vegetated Vertical Accuracy 95th Percentile	N/A	13.56	30.0	12.05

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.

Classification ID	Classification Type		
1	Unclassified		
2	Ground		
7	Low Point		
9	Water		
17	Bridge Deck		
18	High Noise		
20	Ignored Ground		

Sensor(s) Used

Sensor
Optech Galaxy ALTM - Aerial Oscillating Mirror





Work Unit Information

MN_BeckerCo_1_2021	Work Unit ID: 223404	Quality Level: 1	
Horizontal EPSG Code: 6344	Vertical EPSG Code: 5703	Geoid Model: GEOID18	
DEM Ground Sample Distance: 0.5	Hydro Treatment: hydro-flattened		
Collection Start Date: 2022-05-15	Collection End Date: 20	022-09-18	





Project Name: MN_BeckerCounty_2021_D21