NM_NRCS_MiddleRioGrande_2017_D18



Project Definition: The entire collection for a contracted area.

Work Unit Definition: A production block of data defined by the National Geospatial Technical Operations Center due to expediency, priority or resource allocation. There can be one or many work units per project.

Project Information

Lidar Base Specification: 1.3	Primary Contractor: The Atlantic Group, LLC		
Las Version: 1.4	Contract Mechanism: GPSC		
P Method: 7 - Linear-Mode Lidar	Hydro Treatment: hydro-flattened		
Collection Start Date: 03-18-2018	Collection End Date: 04-22-2018		
The National Map Email: tnm_help@usgs.gov			

Vertical Accuracy Results

The U.S. Geological Survey evaluates absolute vertical accuracy	II IOAF POINT CIOUO		Digital Elevation Model	
of the lidar and lidar-derived bare earth DEM data at the project level	Required Value(cm)	Tested Value (cm)	Required Value(cm)	Tested Value (cm)
Non-Vegetated Vertical Accuracy 95-Percent Confidence Level	19.6	15.13	19.6	15.05
Vegetated Vertical Accuracy 95th Percentile	N/A	17.01	30.0	16.64

Please see the vertical_accuracy folder within the project metadata for more information.

Classifications Used

Classification verification is limited to the minimum required by applicable Lidar Base Specification. Classifications beyond the minimum are not verified by USGS.				
Classification ID	Classification Type			
1	Processed, But Unclassified			
2	Bare Earth			
7	Low Noise			
9	Water			
17	Bridge Decks			
18	High Noise			
20	Ignored Ground			

Sensor(s) Used

Sensor
Leica ALS70 - Aerial Oscillating Mirror





Project Name: NM_NRCS_MiddleRioGrande_2017_D18

Report Date: 2022-01-05

Work Unit Information

NM_NRCS-MiddleRioGrande_2017	Work Unit ID: 77895	Quality Level: 2
Horizontal EPSG Code: 6342	Vertical EPSG Code: 5703	Geoid Model: GEOID 12B
DEM Ground Sample Distance: 1.0		
Collection Start Date: 2018-03-18	Collection End Date: 2018-04-22	





Project Name: NM_NRCS_MiddleRioGrande_2017_D18

Report Date: 2022-01-05